



Abel Recon

P.O. Box 476, Mountville, PA 17554 - 0476 • 717/285-3103
Fax 717/285-2321 • www.abelrecon.com

January 3, 2025

COSTARS Vendor #: 317637
COSTARS Contract #: 041-E23-028

West Vincent Twp
729 St. Matthews Rd
Chester Springs, PA 19425

Attention: Mr. Norm Ulrich

RE: WEST VINCENT TOWNSHIP STORM PIPE LINING PROPOSAL

Mr. Ulrich,

We are pleased to submit the following for your above referenced project located in West Vincent Township, Chester County, Pennsylvania under COSTAR Contract # 041-E23-028. When accepted by you below, this will constitute our contract with respect to the work which is described in this proposal.

CURED-IN-PLACE PIPE LINING SCOPE OF WORK:

1. Light cleaning (a maximum of 3 passes with a high-pressure cleaning nozzle). Any cleaning requiring more than 3 passes with a high-pressure cleaning nozzle will be deemed heavy cleaning and will be billed in addition to the original proposed amount on a time and material basis.
2. Pre-televiser and evaluate host pipe.
3. Install 36-inch, 18-inch and 27x42-inch Alphasliner with integrated slip sheet, totaling approximately 130 LF, 93 LF and 100 LF respectively. Installation will follow Reline America, Inc. design and recommendations.
4. Reinstate (0) service laterals.

CURED-IN-PLACE PIPE LINING SCOPE OF WORK (continued):

5. If the ends of the 36" pipe runs are not tight to the pipe at the inlets the liner will be cut back until it is tight to the host pipe the remaining unlined host pipe will be sprayed with Spraywall at a thickness of 300 mils.
6. Township to remove tops/risers from inlets in the ponds
7. Township to provide traffic control for the lining operations.
8. Post-televised installed product.
9. By-pass pumping up to 350 gpm.
10. The following items are excluded from the present scope of work, and if required, shall be performed on a time and material basis and charged in addition to the proposal amount.
 - a. Work related to the removal of temporary erosion control measures, site stabilization, installation of matting and seeding.
 - b. Any necessary site clearing, as required for access to the work area. Access must be suitable for 2-wheel drive box truck vehicles.
 - c. Any repairs completed by excavation.
 - d. Access agreements and property owner coordination.
 - e. By-pass pumping above 350 gpm.
 - f. Chemical grout application to stop severe infiltration.
 - g. Material testing.
 - h. Protruding lateral removal and lateral root removal.
 - i. Safety orientation requirements that may be required by Owner and/or General Contractor.

GENERAL NOTES:

1. Damage caused by others, to an item constructed under this contract, will not be the responsibility of Abel Recon. In addition, when a given item of work is tested and inspected by the governing authority, that item becomes the responsibility of the Owner to protect and maintain.
2. Prices for this project shall remain firm for 30 calendar days from the date of the proposal. Abel Recon reserves the right to review all prices after that date.
3. Invoices shall be submitted twice monthly. Payment shall be due within thirty (30) days after completion of the work invoiced. Abel Recon reserves the option to charge interest on any monies owed after thirty (30) days. Interest, if assessed, will be at Fulton Bank prevailing prime plus 2%. Abel Recon will invoice for work completed only, **and will not be subject to any contract retainage.**
4. Any alteration is to be agreed upon in writing by the Owner and Abel Recon.
5. Proposal is based on Non-Prevailing Wage Rates.
6. Abel Recon reserves the right to set schedules based on weather, temperature conditions and equipment availability.
7. The recommended nozzle pressure when jetting the interior of a CIPP lined pipe is 1,300 PSI. It is imperative that this level of pressure be maintained in conjunction with a wide spray nozzle with a maximum spray angle of 40°. The pressure used within the liner should never exceed **1,300 PSI**, this could result in damage or subsequent failure of the liner.
8. This Proposal does not include any Bonds or Permits.
9. Any dispute under this contract shall be resolved in Lancaster County, Pennsylvania and will be interpreted under Pennsylvania law including, but not limited to, the Contractor Act and Subcontractor Payment Act.


PROPOSAL BREAKDOWN:

18-inch Pipe Lining	-	\$19,700.00
36-inch Pipe Lining	-	\$67,600.00
27x42-inch Pipe Lining	-	\$69,700.00

Thank you for the opportunity to quote this project. Should you accept this proposal, please sign, date and return proposal to my attention. The purchase order should include the COSTARS Contract Number and your COSTARS Member Name and Number.

Respectfully submitted,

ABEL RECON



DAVID HOPKINS
Project Manager



HOWARD D. MYERS
General Manager

ACCEPTED:

West Vincent Township

Date

(Print Name and Title)



Abel Recon

P.O. Box 476, Mountville, PA 17554 - 0476 • 717/285-3103
Fax 717/285-2321 • www.abelrecon.com

ACCOUNTING PROJECT SET-UP AND CONTACT INFORMATION

Check box if the contact information is the same for all documents.

ACCOUNTS PAYABLE INFORMATION:

Contact Person: _____

Mailing Address: _____

Phone Number: () _____

Email Address: _____

VIDEOS, REPORTS, AS-BUILTS, ETC:

Contact Person: _____

Mailing Address: _____

Phone Number: () _____

Email Address: _____

CERTIFIED PAYROLL, IF APPLICABLE:

Contact Person: _____

Mailing Address: _____

Phone Number: () _____

Email Address: _____